

1. **Closed or open transfer switch?**

ATS shall be open transition style.

2. **What is the expected duration run time?**

Fuel capacity shall be rated for 24 Hours at Full Load

3. **Question about the annual load bank test?**

A load bank test shall be required as part of commissioning. An annual load bank test would be considered as general maintenance and should not be included in the bids.

4. **Would you accept a quote for a Kohler or blue star generator?**

Kohler is acceptable. Blue Star is not an acceptable alternate.